SECTION 00020

INVITATION TO BID

CITY OF BRUSH!
ELM STREET IMPROVEMENTS

Sealed bids for the Elm Street Improvements shall be received by the **OWNER**, City of Brush! located at 600 Edison Street Brush, Colorado 80723 until **10:00 AM., local time, March 3, 2017**, at which time the bids will be publicly opened and read aloud at the same location.

The Contract Documents consisting of a Project Manual and Drawings may be obtained by either electronic documents on-line on and after 2:00 P.M., Wednesday February 8, 2017. Complete electronic Project Plans, Project Specifications, and Bid Proposal Packet are available at the JDS-Hydro Consultants, Inc. website "www.jdshydro.com", click on the "Browse Current Projects" link and select this project from the project list. Documents cannot be downloaded or printed without purchasing. To purchase and download the project documents in pdf format, click "Download Project PDF" and sign on to QuestCDN.com or join for a free membership. Plan documents can be downloaded for a fee of $10.00. Please contact QuestCDN at 952-233-1632 or email "info@questcdn.com" for assistance in the free membership registration, downloading, and working with this digital project information. In addition, the Drawings and Project Manual may be examined at the following locations: the office of the consulting engineer, JDS-Hydro Consultants, Inc, and through the City of Brush!.

The successful **BIDDER** will be required to furnish Payment and Performance Bonds and comply with the insurance provision as specified by the Contract Documents. A 5% Bid Bond will be required.

A description of the work to be performed generally includes: **removal of 2490 SF of sidewalk; removal of 2520 SY of compacted gravel; preparation of subgrade, including scarification to a depth of 9" and recompaction; placement and compaction of 2382 SY of aggregate base course to a depth of 7"; paving with 2382 SY of asphalt (Grading S or SX); installation of 830 LF of 6" vertical curb and gutter; installation of 306 SF of 6'-wide concrete pan; installation of two (2) pedestrian ramps; construction of 2905 SY of 3.5'-wide concrete sidewalk; sawcutting of 80 LF of asphalt and 10 LF of concrete; patching of 17 SY of 2'-wide asphalt patch; and removal and replacement of 100 SY of residential sidewalk and driveway. Included is all site work, earth work, erosion control, traffic control, construction surveying, installation, and incidental work required to complete the Work as specified on the Drawings.**

Qualifications to the **BIDDER** should include: experience in asphalt paving and concrete flatwork construction, ability to obtain necessary permits for construction, ability to post performance and payment bonds, and ability to deliver the work in conformance with specifications within the contract time.

A **mandatory pre-bid meeting is set for 11:00 AM, February 23, 2017** at 600 Edison Street Brush, CO 80723.

Prospective Bidders may visit the site between the hours of 8:00 a.m. and 4:00 p.m. on weekdays. The City of Brush, Dale Colerick, may be reached at (970) 842-5001; however, technical questions must be directed to the ENGINEER at (719) 227-0072 (Geoffrey Sanders).

The **OWNER** reserves the right to waive any irregularities or to waive any technical defects in the bidding process as the best interest of the **OWNER** may be served. The **OWNER** also reserves the right to reject any and all bids. Basis of award will be the lowest responsive and responsible Bid as determined by the **OWNER**.

City of Brush!

By_____Dale Colerick, Director of Public Works___

Publication Dates: **Brush News Tribune – February 8, 15, and 22, 2017**
Fort Morgan Times – February 8, 15, and 22, 2017